


## **USCG ANT PUERTO RICO**

CHRISTIANSTED, ST. CROIX U.S. VIRGIN ISLANDS




# HS17B REBUILD CHRISTIANSTED HARBOR CHANNEL LIGHTS (LT 7, 9, 10, 11, 13, DBN 16, & COAKLEY BAY LT1)

**JUNE 2020** 



	LIS	T OF DRAWINGS
SHT. NO.	DISCIPLINE SHEET NO.	TITLE
		<u>GENERAL</u>
1	G-01	COVER SHEET
		<u>CIVIL</u>
2	C-01	OVERALL SITE PLAN
3	C-02	TOWER SITE PLANS
4	C-03	PHOTOGRAPHS
5	C-04	RANGE REMOVALS
		STRUCTURAL
6	S-01	STRUCTURAL NOTES
7	S-02	TOWER ELEVATIONS
8	S-03	TOWER PLANS
9	S-04	JACKET ELEVATIONS
10	S-05	JACKET SECTIONS
11	S-06	DETAILS - 1
12	S-07	DETAILS - 2
13	S-08	DETAILS - 3



## **ELEVATION, SECTION OR DETAIL SYMBOLS**

SHFFT NUMBER WHERE ELEVATION IS SHOWN

## **EXTERIOR ELEVATION/SECTION**

REFERENCE OLIADRANT SHEET NUMBER WHERE

REFERENCE QUADRANT SHEET NUMBER WHERE

**DETAIL** 

M.A. BRAXTON E. SAN

PROJECT ENG. BRANCH CHIEF TECH. DIRECTO PROJECT NUMBER DRAWING NUMBER 10251739 M2329-D SHEET 1 OF 13

HS17B REBUILD CHRISTIANSTED HARBOR CHANNEL LIGHTS

USCG ANT PUERTO RICO

GENERAL

M.J. LESINSK

COVER SHEET

**Appledore Marine Engineering, LLC** 

U. S. COAST GUARD CIVIL ENGINEERING UNIT

USCG. CEU MIAMI 15608 SW 117TH AVE MIAMI, FLORIDA 33177

A/E PROJECT NO:8021 CAD FILE NAME: M2329-D G01.D

600 State Street, Suite E Portsmouth, New Hampshire 03801 (603) 766-1870 amei@appledoremarine.com

## TIDAL DATUMS (1983-2001 TIDAL EPOCH) MEAN HIGHER HIGH WATER (MHHW) 0.72 MEAN LOW WATER (MLW) 0.03 MEAN LOWER LOW WATER (MLLW) NOAA/NOS TIDE STATION ID# 9751364, ST. CROIX, USVI

ALL ELEVATIONS REFERENCE MLLW UNLESS OTHERWISE NOTED

ATON AIDS TO NAVIGATION NOT TO SCALE CENTER LINE RADIUS RANGE FRONT LIGHT DIAMETER ELEVATION IN FEET MAXIMUM SCHEDULE MEAN HIGH WATER MEAN HIGHER HIGH WATER TO BE DETERMINED MEAN LOW WATER



TOWER SUMMARY								
	TOWER	NORTHING	EASTING	LATITUDE	LONGITUDE	WATER DEPTH	FOCAL HEIGHT	DECK ELEVATION
	CHANNEL LIGHT 7	6,443,997.39	1,051,033.85	N 17 45 25.811	W 64 41 40.040	22 FT	16.72 FT	12.3 FT
	CHANNEL LIGHT 9	6,433,698.22	1,049,647.10	N 17 45 22.721	W 64 41 54.360	18 FT	16.72 FT	12.3 FT
	CHANNEL LIGHT 10	6,443,972.24	1,049,005.88	N 17 45 25.38	W 64 42 01.020	17 FT	17.72 FT	12.3 FT
	CHANNEL LIGHT 11	6,443,453.22	1,049,411.85	N 17 45 20.271	W 64 41 56.771	12 FT	16.72 FT	12.3 FT
	CHANNEL LIGHT 13	6,441,749.97	1,049,408.14	N 17 45 03.385	W 64 41 56.650	19 FT	16.72 FT	12.3 FT
	DAYBEACON 16	6,440,527.31	1,048,696.33	N 17 44 51.200	W 64 42 03.900	19 FT	16.72 FT*	12.3 FT
	COAKLEY BAY LIGHT 1	6,447,142.66	1,070,189.85	N 17 45 58.679	W 64 38 22.123	18 FT	16.72 FT	12.3 FT

\* DAYBOARD HEIGHT

NOTE:

1. COORDINATES, AS PROVIDED BY USCG, REPRESENT THE LOCATION OF THE LANTERN SUPPORTED BY THE TOWER STRUCTURE. CHANNEL LIGHT 10 AND COAKLEY BAY COORDINATES BASED ON AME FIELD INVESTIGATION. CONFIRM ALL COORDINATES PRIOR TO CONSTRUCTION.

2. WATER DEPTHS ARE BELOW MILLY AND ARE APPROXIMATE BASED ON LEAD LINE MEASUREMENTS REFERENCED TO THE WATER LEVEL AND CORRECTED FOR THE REPORTED TIDES FROM NOAA.

3. HORIZONTAL DATUM IS BASED ON GEOGRAPHIC COORDINATES (LAT/LONG), NORTH AMERICAN DATUM OF 1983 (NAD83).

## **GENERAL NOTES:**

2

- THE DRAWINGS AND SPECIFICATIONS FORM A PART OF THE CONTRACT DOCUMENTS AND ALL WORK MUST BE PERFORMED IN ACCORDANCE WITH THE CONTRACT DOCUMENTS. A COPY OF THE DRAWINGS AND THE SPECIFICATIONS MUST BE KEPT ON SITE AT ALL TIMES DURING THE
- 2. IT IS RECOMMENDED THAT A PRE-BID SITE VISIT BE COMPLETED TO VERIFY THE PROJECT SCOPE AND EXTENT OF WORK.
- 3. DIMENSIONS AND DETAILS OF THE EXISTING ELEMENTS ARE BASED ON LIMITED ARCHIVE DRAWINGS FURNISHED BY THE U.S. COAST GUARD. WORK RELATED DIMENSIONS AND DETAILS OF THE EXISTING ELEMENTS MUST BE FIELD VERFIELD. DISCREPANCIES MUST BE BROUGHT TO THE ATTENTION OF THE GOVERNMENT BEFORE ORDERING MATERIALS AND PROCEEDING WITH
- SCHEDULE AND COORDINATE ALL WORK, INCLUDING ALLOWABLE WORK WINDOWS, WITH THE GOVERNMENT, AND MAINTAIN THE WORK SITE TO THE SATISFACTION OF THE GOVERNMENT.
- 5. PROVIDE AND MAINTAIN ENVIRONMENTAL CONTROLS AS REQUIRED BY FEDERAL, STATE AND LOCAL REGULATIONS AND PERMITS. ENVIRONMENTAL CONTROLS MUST INCLUDE BUT NOT BE LIMITED TO TURBIDITY AND DUST.



SCALE: NOT TO SCALE

**Appledore Marine Engineering, LLC** 

600 State Street, Suite E Portsmouth, New Hampshire 03801 (603) 766-1870 amei@appledoremarine.com

CONSULTANTS

U. S. COAST GUARD CIVIL ENGINEERING UNIT MIAMI



USCG. CEU MIAMI 15608 SW 117TH AVE MIAMI, FLORIDA 33177

ISSUE		
MARK	DATE	DESCRIPTION
 1		

A/E PROJECT NO	: 8021
CAD FILE NAME:	M2329-D C01.DWG
DESIGNED BY:	LAH
DRAWN BY:	SND
EDITED BY:	SND
CHECKED BY:	NJE

SCALE: AS SHOWN PLOT SCALE: 1:1

SHEET TITLE

2%

HS17B REBUILD CHRISTIANSTED HARBOR CHANNEL LIGHTS USCG ANT PUERTO RICO ST. CROIX


> CIVIL SITE PLAN


REVIEWED BY: REVIEWED BY: REVIEWED BY: E. SAN M.A BRAXTON M.J. LESINSKI PROJECT ENG. BRANCH CHIEF TECH. DIRECTOR M.J. LESINSKI APPROVING OFFICER DATE 

PROJECT NUMBER DRAWING NUMBER 10251739 M2329-D DISCIPLINE/SHT NO SHEET 2 OF 13 C - 01

3

**KEY PLAN** 





Appledore Marine Engineering, LLC

U. S. COAST GUARD CIVIL ENGINEERING UNIT MIAMI



ISSUE		
MARK	DATE	DESCRIPTION
_		

	: 8021	
	CAD FILE NAME:	M2329-D C02.DWG
	DESIGNED BY:	LAH
	DRAWN BY:	SND
	EDITED BY:	SND
	CHECKED BY:	NJE


SCALE: AS SHOWN PLOT SCALE: 1:1

HS17B REBUILD CHRISTIANSTED HARBOR CHANNEL LIGHTS
USCG ANT PUERTO RICO
ST. CROIX USVI

CIVIL PHOTOGRAPHS

Ŋ	REVIEWED BY:	REVIEWED BY:	REVIEWED BY
7	M.A. BRAXTON	E. SAN	M.J. LESINS
	PROJECT ENG.	BRANCH CHIEF	TECH. DIREC
$\geq$			
	M.J. L		
	APPROVI	DATE	

DRAWING NUMBER M2329-D C-03 SHEET 4 OF 13



### ATON TOWER NOTES:

- ALL DIMENSIONS, ELEVATIONS AND CONDITIONS SHALL BE VERIFIED IN THE FIELD BY THE CONTRACTOR. ANY DISCREPANCIES SHALL BE BROUGHT TO THE ATTENTION OF THE CONTRACTING OFFICER BEFORE ORDERING MATERIALS AND PROCEEDING WITH THE AFFECTED PART OF THE WORK.
- CONTRACTOR SHALL MAINTAIN ADEQUATE SURVEY CONTROL AT ALL TIMES TO ESTABLISH AND MAINTAIN ALL LINES AND ELEVATIONS.
- STRUCTURAL STEEL CONSTRUCTION SHALL CONFORM TO THE LATEST EDITION OF THE STEEL CONSTRUCTION MANUAL OF THE AMERICAN INSTITUTE OF STEEL CONSTRUCTION, UNLESS OTHERWISE DETAILED.
- 4. ALL STRUCTURAL STEEL SHAPES SHALL BE ASTM A572, GRADE 50 UNLESS OTHERWISE NOTED:
- a. STEEL PIPE PILES, ASTM A252, GRADE 3 SEAMLESS OR STRAIGHT SEAM.
- b. STEEL PIPE HANDRAILS ASTM A53, TYPE E OR S, GRADE B.
- 5. ALL STRUCTURAL MEMBERS AND CONNECTIONS SHALL BE PROVIDED WITH COATING AND CORROSION PROTECTION SYSTEM IN ACCORDANCE WITH THE SPECIFICATIONS.
- SUBMIT DETAILED SHOP DRAWINGS TO THE CONTRACTING OFFICER FOR REVIEW AND APPROVAL PRIOR TO THE FABRICATION OR DELIVERY OF ANY STEEL.
- 7. ALL BOLTS SHALL BE ASTM A307 UNLESS NOTED OTHERWISE.
- 8. ALL CONNECTIONS SHALL BE MADE WITH A 5/16" FILLET WELD OR PARTIAL PENETRATION GROOVE WELD, UNLESS NOTED OTHERWISE. ALL WELDS REGARDLESS OF TYPE SHALL BE WELDED ALL AROUND AND CONFORMING TO AWS D1.1 AND BE MADE WITH E70-XX ELECTRODES. ALL WELDS TO COMPLETELY SEAL CONNECTIONS.
- LIGHTNING PROTECTION SHALL HAVE A SINGLE AIR TERMINAL WITH TIP MOUNTED 10" HIGHER THAN
  THE HIGHEST POINT ON THE TOWER OR ANY APPURTENANCE.
- 10. OUTFIT ALL LADDERS WITH A CABLE SAFETY CLIMB SYSTEM.
- 11. DECKING SHALL BE FIBERGLASS REINFORCED PLASTIC (FRP) GRATING AND ANCHORED TO THE FRAMING USING PRE-WELDED STUDS TO PREVENT DAMAGE TO THE COATING SYSTEM.
- 12. ALL HANDRAILS, LADDERS AND OTHER SAFETY FEATURES SHALL MEET THE REQUIREMENTS OF OSHA

## STEEL TREATMENT NOTES:

- 1. THE INTEGRITY OF THE COATING SYSTEM IS PARAMOUNT TO THE DESIGN SERVICE LIFE AND REQUIRES SPECIAL CARE DURING CONSTRUCTION TO MINIMIZE DAMAGE.
- 2. THE PROJECT HAS BEEN SPECIFICALLY DESIGNED TO MINIMIZE FIELD WELDING AND THE EXPECTATION IS THAT ALL WELDING WILL BE COMPLETED IN THE FABRICATION SHOP PRIOR TO COATING.
- APPURTENANCES SUCH AS THE GRATING, HANDRAILS, LIGHTS, ETC. SHALL BE FABRICATED WITH PRE-WELDED ATTACHMENT STUDS OR MALE/FEMALE CONNECTIONS TO ALLOW ATTACHMENT IN THE FIELD WITHOUT WELDING.
- 4. APPLY JOINT SEALANT TO BACK-TO-BACK STEEL BOLTED CONNECTIONS.

## DESIGN INTENT NOTES:

- THE PREFABRICATED STEEL JACKET PROVIDES CORROSION PROTECTION AND WILL ALSO BE USED AS A PILE DRIVING TEMPLATE TO ALLEVIATE THE NEED OF ADDITIONAL TEMPORARY FALSEWORK.
- THE CENTRAL TUBE IN THE JACKET, IN CONJUNCTION WITH A TEMPORARY POSITIONING PILE (NOT SHOWN FOR CLARITY) SHALL BE USED TO LOCATE THE NEW TOWER STRUCTURE AND TO ORIENT/TEMPORARILY SUPPORT THE JACKET DURING BATTER PILE INSTALLATION.
- 3. DRIVE PIPE PILES THROUGH THE JACKET SLEEVES TO THEIR DESIGN TIP ELEVATION. CUT PILES 1' BELOW TOP OF JACKET AND GROUT THE ANNULUS BETWEEN THE JACKET AND PILES.

2

4. REMOVE THE TEMPORARY POSITIONING PILE ONCE THE BATTER PILES AND JACKET HAVE BEEN GROUTED.

Appledore Marine Engineering, LLC

600 State Street, Suite E Portsmouth, New Hampshire 03801 (603) 766-1870 amei@appledoremarine.com

CONSULTANTS

C

U. S. COAST GUARD CIVIL ENGINEERING UNIT MIAMI



USCG. CEU MIAMI 15608 SW 117TH AVE MIAMI, FLORIDA 33177

MARK DATE DESCRIPTION

A/E PROJECT NO: 8021

CAD FILE NAME: M2329—D C02:DWG

DESIGNED BY: LAH

DRAWN BY: SND

EDITED BY: SND

CHECKED BY: NJE

SCALE: AS SHOWN PLOT SCALE: 1:1

SHEET TITLE

S

HS17B REBUILD CHRISTIANSTED HARBOR CHANNEL LIGHTS
USCG ANT PUERTO RICO
ST. CROIX
USVI

STRUCTURAL STRUCTURAL NOTES

REVIEWED BY: REVIEWED BY: REVIEWED BY:

M.A. BRAXTON E. SAN M.J. LESINSKI
PROJECT ENG. BRANCH CHIEF TECH. DIRECTOR

M.J. LESINSKI
APPROVING OFFICER DATE

 PROJECT NUMBER
 DRAWING NUMBER

 1 0 2 5 1 7 3 9
 M2 3 2 9 - D

 DISCIPLINE/SHT NO
 SHEET 6 OF 13

3 4

